

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF ALTERNATES

A. ALTERNATE BID ITEM NO. 1:

PARKING AREA - STORMWATER MITIGATION, ASPHALT MILLING, RESURFACE AND RESTRIPE. CONNECT MAIN ARMORY ROOF DRAINS TO UNDERGROUND STORM DRAIN SYSTEM.

B. ALTERNATE BID ITEM NO. 2:

UPGRADE MAIN ARMORY BUILDING INTERIOR AND EXTERIOR LIGHTING TO LED TO INCLUDE UNIT SIGN AND FLAGPOLE.

C. ALTERNATE BID ITEM NO. 3:

REFINISH AND REPAINT COMPLETE EXTERIOR STUCCO / BRICK FACADE WITH UP TO 4 COLOR SCHEME. REFINISH AND REPAINT COMPLETE EXTERIOR HIGH BAY MAINTENANCE SHELTER WITH HIGH PERFORMANCE PAINTED FINISH.

D. ALTERNATE BID ITEM NO. 4:

COMPLETE GLAZING REPLACEMENT OF ALL EXISTING LAMINATED IMPACT GLAZING IN EXISTING ALUMINUM WINDOW FRAME SYSTEMS AT THE EXTERIOR CLERESTORY LEVEL.

E. ALTERNATE BID ITEM NO. 5:

COMPLETE GLAZING REPLACEMENT OF ALL EXISTING LAMINATED IMPACT GLAZING IN ALL EXISTING ALUMINUM WINDOW FRAME SYSTEMS AT ALL THE EXTERIOR 1ST FLOOR LEVEL GLAZED OPENINGS EXCEPT NEW EXTERIOR FIXED WINDOWS & IMPACT GLAZING FOR KITCHEN ONLY.

F. ALTERNATE BID ITEM NO. 6:

PROVIDE NEW 20'-0" WIDE (K-8 FORCE PROTECTION) FENCE SYSTEM) SLIDING GATE WITH MANUAL FUNCTION TO SOUTH SIDE OF POV PARKING. EXISTING DEAD MAN ANCHOR LAYOUT TO BE RE-CONFIGURED FOR NEW GATE. COMPLETE FUNCTIONAL INSTALLATION REQUIRED.

G. ALTERNATE BID ITEM NO. 7:

PROVIDE MILL AND OVERLAY OF THE FRONT POV PARKING LOT AS INDICATED IN THE ATTACHED CIVIL DRAWINGS.

THE STATE OF FLORIDA DEPARTMENT of MILITARY AFFAIRS / CFMO Project # 224004
100% CONSTRUCTION DOCUMENT SPECIFICATIONS
PALMETTO ESP RENOVATION

H. ALTERNATE BID ITEM NO. 8:

PROVIDE NEW DEHUMIDIFIER AND MECHANICAL AIR INSTALLED INTO THE TO
THE EXISTING VAULT ROOM # 110 & #111.

END OF SECTION 01 2300