

**BIDDING AND CONTRACT DOCUMENTS
FOR THE
TOWN OF CARY, NORTH CAROLINA
2026 FORCE MAIN INSPECTION AND MAINTENANCE PROJECT**

ADDENDUM NO. 1

Date Issued:

June 5, 2026

Bidders on this Project are hereby notified that this Addendum shall be attached to and made a part of the above named Bidding and Contract Documents dated May 2026.

The following items are issued to add to, modify, and clarify the Bidding and Contract Documents. These items shall have full force and effect as the Bidding and Contract Documents, and cost involved shall be included in the bid prices. Bids, to be submitted on the specified bid date, shall conform with the additions and revisions listed herein.

Acknowledge receipt of the Addendum by inserting its number and date on specified page of the bid documents. Failure to do so may subject the bidder to disqualification.



6/5/2026

BID OPENING INFORMATION:

1. The bid opening remains at 11:00 a.m. on Tuesday, June 23, 2026 at Cary Town Hall, 316 North Academy Street, Cary, North Carolina, 1st Floor - Conference Room 11130

IN THE SPECIFICATIONS:

SECTION 00250 INSTRUCTIONS TO BIDDERS

1. DELETE the fourth paragraph in bold on page 00250-1 and replace with the text below:

“A pre-bid meeting will be held with the Engineer and Owner at 10:30 a.m. on Thursday June 11, 2026 in Conference Room 11130 – 1st Floor of Town Hall, 316 North Academy Street, Cary, North Carolina to discuss the project and answer pertinent questions. No oral interpretations will be made as to the meaning of the Contract Documents. Interpretation, if deemed necessary, will be in the form of a written Addendum.”

SECTION 21000 SPECIAL CONSTRUCTION

1. ADD the following text after Part 10.A:

A.“B. Approximate pump station inflow: The flows provided in the table below are based upon typical run times and pump flow rates. This information is for general, order-of-magnitude flow estimates for pump and haul planning only. Flows will vary depending on wet verses dry conditions.

Pump Station	Typical Flow (gpd)
Holly Brook	50,000 ±
Rocky Branch	25,000 ±
Forest Oaks	103,000 ±
Medfield	104,000 ±

”

2. ADD the following text after the payment section of Part 12.B (Bid Items), Section D.4 (Locate and Replace ARV Manhole):

A.“The following internal pipe, fittings, and materials for the Forest Oaks ARV manhole will be provided by the Owner, and installed by the Contractor:

- 10” x 4” Tee
- 4” Blind Flange Tapped for 2” pipe nipple
- 2” stainless steel pipe nipple
- 2” stainless steel ball valve
- 2” ARV
- 10” wedge restraint glands (a.k.a Megalugs)
- 10” MJ kits (gaskets & bolts)
- 10” Ductile Iron Pipe

All other materials required shall be provided by the Contractor.”

ATTACHMENTS

1. None

END OF ADDENDUM 1