ID FLAP ADA 2019(1), Western Heritage Byway - Swan Falls Road
Ada County, Idaho

This work consists of shoulder widening, paving, signage, parking lot improvement, and culvert replacement.

Project length:

Schedule A – 3.25 miles
Schedule B – 3.82 miles
Schedule C – 4.94 miles
Schedule D – 8.50 miles

There are 4 bid schedules; only 1 bid schedule will be awarded.

Tentative Fixed Completion Date: Summer/Fall 2027
(Once solicitation is issued, see SF1442 Continuation, Block 11 for exact date.)

Tentative Solicitation Date: Summer 2026

Estimated Price Range: $5 million to $10 million

Location: 7 miles south of Kuna, Idaho

DESCRIPTION OF WORK in US CUSTOMARY UNITS
FP-24

	Schedule A	Schedule B	Schedule C	Schedule D
DIVISION 150 – Project Requirements				
152 Construction Survey & Staking **(yes/no)**	**Yes**	**Yes**	**Yes**	**Yes**
153 Contractor Quality Control **(yes/no)**	**Yes**	**Yes**	**Yes**	**Yes**
154 Contractor Sampling & Testing **(yes/no)**	**Yes**	**Yes**	**Yes**	**Yes**
155 Schedules for Construction Contracts *(construction schedules)* **(yes/no)**	**Yes**	**Yes**	**Yes**	**Yes**
157 Soil Erosion & Sediment Control, *Fiber Roll*	**10,500 LNFT**	**10,700 LNFT**	**17,500 LNFT**	**17,500 LNFT**
158 Watering for Dust Control	**LPSM**	**LPSM**	**LPSM**	**LPSM**
DIVISION 200 – Earthwork				
201 Clearing & Grubbing	**9 ACRE**	**9.5 ACRE**	**13 ACRE**	**13 ACRE**
203 Removal of Cattle Guard	**1 EACH**	**1 EACH**	**1 EACH**	**1 EACH**

	Schedule A	Schedule B	Schedule C	Schedule D
203 Removal of Gate	1 EACH	1 EACH	1 EACH	1 EACH
203 Removal of Restroom Facility	2 EACH	2 EACH	2 EACH	2 EACH
203 Removal of Sign	4 EACH	4 EACH	4 EACH	4 EACH
203 Removal of Vault (Concrete Tanks)	4 EACH	4 EACH	4 EACH	4 EACH
203 Removal of Fence	55 LNFT	55 LNFT	55 LNFT	55 LNFT
203 Sawcutting Pavement	33,880 LNFT	39,900 LNFT	49,000 LNFT	49,000 LNFT
204 Roadway Excavation	13,000 CUYD	14,600 CUYD	18,400 CUYD	18,400 CUYD
204 Rock Excavation	420 CUYD	420 CUYD	420 CUYD	420 CUYD
204 Ditch, Excavation (Regrading)	90 LNFT	90 LNFT	90 LNFT	90 LNFT
204 Remove and Reset Boulder	30 EACH	30 EACH	30 EACH	30 EACH
DIVISION 250 – Slope Reinforcement and Retaining Walls				
251 Placed Riprap, Class 2	5 CUYD	5 CUYD	5 CUYD	5 CUYD
DIVISION 300 – Aggregate and Base Courses				
302 Roadway Aggregate, Method 2	17,000 TON	20,000 TON	24,000 TON	24,000 TON
302 Roadway Aggregate, Method 2, Surface Course, 6-Inch Depth	2,000 SQYD	2,000 SQYD	2,000 SQYD	2,000 SQYD
DIVISION 400 – Asphalt Pavements & Surface Treatments				
403 Asphalt Concrete Pavement	3,600 TON	4,200 TON	6,500 TON	6,500 TON
406 Fog Seal	-	-	-	100 TON
407 Chip Seal, Type 1C	-	-	-	147,500 SQYD
407 Emulsified Asphalt	-	-	-	280 TON
412 Tack Coat	1.5 TON	1.5 TON	5 TON	5 TON
413 Asphalt Pavement Milling, 4-Inch Depth	1,200 SQYD	1,200 SQYD	6,800 SQYD	6,800 SQYD
414 Cracks, Cleaning and Sealing	3.5 MILE	4 MILE	5 MILE	9 MILE
414 Cracks, Cleaning and Filling	3.5 MILE	4 MILE	5 MILE	9 MILE
DIVISION 500 – Rigid Pavement				
501 Minor Concrete Pavement, Plain, 6-Inch Depth	70 SQYD	70 SQYD	70 SQYD	70 SQYD
DIVISION 600 – Incidental Construction				
602 12-Inch Pipe Culvert	-	50 LNFT	50 LNFT	50 LNFT

	Schedule A	Schedule B	Schedule C	Schedule D
602 18-Inch Pipe Culvert	210 LNFT	210 LNFT	210 LNFT	210 LNFT
602 24-Inch Pipe Culvert	270 LNFT	270 LNFT	370 LNFT	370 LNFT
602 End Section for 24-Inch Pipe Culvert	3 EACH	3 EACH	3 EACH	3 EACH
607 Cleaning Culvert In Place	2 EACH	2 EACH	2 EACH	2 EACH
609 Wheelstop, Concrete	2 EACH	2 EACH	2 EACH	2 EACH
610 Sidewalk, Concrete (6-Inch Depth)	300 SQYD	300 SQYD	300 SQYD	300 SQYD
614 Flowable Backfill	13 CUYD	13 CUYD	13 CUYD	13 CUYD
619 Cattle Guard, 32 Feet	1 EACH	1 EACH	1 EACH	1 EACH
619 Remove and Reset Fence	30 LNFT	30 LNFT	30 LNFT	30 LNFT
622 Rental Equipment ***(yes/no)***	Yes	Yes	Yes	Yes
623 General Labor ***(yes/no)***	Yes	Yes	Yes	Yes
624 Providing and Placing Topsoil, 4-Inch Depth	7 ACRE	8 ACRE	9 ACRE	
625 Turf Establishment	7 ACRE	8 ACRE	9 ACRE	
633 Sign System	235 SQFT	235 SQFT	235 SQFT	235 SQFT
633 Object Marker	4 EACH	4 EACH	4 EACH	4 EACH
633 Rumble Strip	32,950 LNFT	38,780 LNFT	50,600 LNFT	50,600 LNFT
634 Pavement Markings, Type B, Solid (White)	69,000 LNFT	81,100 LNFT	105,100 LNFT	180,300 LNFT
634 Pavement Markings, Type B, Solid (Yellow)	51,210 LNFT	58,100 LNFT	74,340 LNFT	126,660 LNFT
634 Pavement Markings, Type B, Broken (Yellow)	15,700 LNFT	19,900 LNFT	26,000 LNFT	39,200 LNFT
634 Pavement Markings, Type B, Accessibility Symbol	4 EACH	4 EACH	4 EACH	4 EACH
635 Temporary Traffic Control, Barricade Type 1	5 EACH	5 EACH	5 EACH	5 EACH
635 Temporary Traffic Control, Barricade Type 3	2 EACH	2 EACH	2 EACH	2 EACH
635 Temporary Traffic Control, Drum	230 EACH	260 EACH	320 EACH	320 EACH
635 Temporary Traffic Control, Portable Changeable Message Sign	2 EACH	2 EACH	2 EACH	2 EACH
635 Temporary Traffic Control, Pavement Markings	430 LNFT	430 LNFT	3,130 LNFT	3,130 LNFT
635 Temporary Traffic Control, Construction Sign	150 SQFT	150 SQFT	150 SQFT	150 SQFT
635 Temporary Traffic Control, Flagger	3,000 HOUR	3,100 HOUR	3,500 HOUR	3,500 HOUR
635 Temporary Traffic Control, Pilot Car	600 HOUR	650 HOUR	900 HOUR	1,070 HOUR
635 Temporary Traffic Control, Traffic Control Supervisor	105 DAY	110 DAY	120 DAY	120 DAY
646 Fixture, Picnic Table	2 EACH	2 EACH	2 EACH	2 EACH
646 Fixture, Vault Toilet	1 EACH	1 EACH	1 EACH	1 EACH
646 Fixture, Shelter (Shade Structure)	1 EACH	1 EACH	1 EACH	1 EACH