DEPARTMENT OF THE AIR FORCE
AIR FORCE LIFE CYCLE MANAGEMENT CENTER
WRIGHT-PATTERSON AIR FORCE BASE OHIO

23 June 2026

FROM: AFLCMC/PZIBA
2275 D Street Building 16, Area B
Wright-Patterson AFB OH 45433

SUBJECT: Response to Inquiries regarding FA8601-26-Q-0070, F20553 Furniture Project 2025SH172

Questions & Answers:

1. Please allow for an extension of an additional 15 business days post receipt of answers.
Answer: The Contracting Officer will not be extending the solicitation proposal due date at this time. This effort was posted on 15 June 2026 and closes on 17 July 2026.

2. There are 2 panel thicknesses requested, please give guidance for requirement of matching finishes and if a limit of one manufacture OR if panels can come from multiple manufactures knowing there will be variation in the final finish package.
Answer: Provide panels from a single manufacturer and matching finishes.

3. HPL tops are requested; would TFL be an acceptable alternative?
Answer: No, TFL is not acceptable.

4. Is fellows Wire Management a requirement or alternatives accepted with similar salient characteristics?
Answer: Alternates are acceptable, equivalent or better.

5. Should base feeds be hardwired? **Yes**
   - Cord length? **Minimum of 72" length**
   - New or existing junction boxes will be needed? **New Junction Box for the D-1, the WS-1, WS-1.1, WS-3, and WS-4 will be powered via base feed with comm pole for network drops. The WS-2 shall have comm pole for network drops and Open Panel Frame underneath worksurface for access to Double Duplex Receptacle Mounted 18" AFF against the wall.**
   - Furniture solution will not include building hook ups, client provided electrician will be needed? **Per the SOW the contractor shall be responsible for supplying all labor and materials when applicable for a Certified Electrician from Master Electrical Contractors Association (MECA) to hook up the Systems Furniture to Building power, to accomplish this project in accordance with the Statement of Work (SOW), project drawings.**

6. A t-2 table is pictured on the ID-3 floorplan but not listed in the furniture characteristics document. Please let us know if it is not in the scope of work or what the characteristics required are.
   Answer: See revised SOW that incudes the T-2 Table and specifications.

7. WS-1 -
   - Is a total height of 98" the requirement? (+/-3") - **Yes**
     - If so, is the glass topper trim intended to connect into the ceiling grid? – **No**

8. D-1 -
   - For the 16" segmented tile, please elaborate on the frosted acrylic finish request. **It's White Opaque Acrylic Tile.** Are alternatives acceptable? Fabric, whiteboard, steel (with multiple painted color choices). **Steel (with multiple painted color choices) is acceptable.**
   - Is fellows power a requirement or can we provide an alternative to that manufacture? **Alternates are acceptable, equivalent or better.**
   - Furniture solution does not include adding junction boxes, in this case to the ceiling, please confirm if you will provide an electrician or if we should include an electrician in our bid pricing. **Per the SOW include and electrician in your pricing.**

9. Seating -
   - If an alternative seating manufacture is the proposed solution, do they need to match the fabric grade or is a fabric that has a similar look acceptable? **Match the fabric grade.**

SNOW.CANDICE.LYNN.1423542060
Digitally signed by SNOW.CANDICE.LYNN.1423542060
Date: 2026.06.23 08:27:30 -04'00'

CANDICE SNOW
AFLCMC/PZIBA, Contracting Officer