SHEET NO.	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY201A	001	01BA01	1	B	SB-09-1	STAIR #9		SB-09-1	STAIR #9				GC-052	FOC
	002	01BA02	1	B	AB-4	LOBBY		AB-4	LOBBY				GC-052	FOC
	003	01BA03	1	B		EXTERIOR DOOR			EXTERIOR DOOR				GC-052	FOC
	004	01BA05	1	B	AB-5	RECORDS STORAGE		AB-5	RECORDS STORAGE	X			GC-052	FOC
	005	01BA07	1	B		SOUTH EAST LOUVERS		AB-1	MECHANICAL				GC-052	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY201B	006	01BB01	1	B		SOUTH STAIR			SOUTH STAIR				GC-052	FOC
	007	01BB02	1	B		WEST STAIR			WEST STAIR				GC-052	FOC
	008	01BB04	1	B	BB-1d	WORK AREA	ENTRANCE RAMP	BB-1d	WORK AREA	X			GC-052	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY201C	009	01BC02	1	B	SB-20-1	STAIR #20		SB-20-1	STAIR #20				GC-052	CAT6E
	010	01BC03	1	B		ELEV. LOBBY		CB-??	CORRIDOR				GC-052	CAT6E
	011	01BC04	1	B		WEST STAIR			WEST STAIR				GC-052	FOC
	012	01BC05	1	B		NORTH STAIR			NORTH STAIR				GC-052	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY201D	013	01BD03	1	B	BD-10	MECHANICAL	ENTRANCE FROM RAMP FROM DOCK AREA	BD-10	MECHANICAL				GC-052	FOC
	014	01BD04	1	B	BD-10	MECHANICAL	ELECTRICAL AND COMM ROOM ENTRANCES	BD-10	MECHANICAL	X			GC-052	FOC
	015	01BD05	1	B	SB-22-1	STAIR #22		SB-22-1	STAIR #22				GC-052	FOC
	016	01BD06	1	B	DB-2	RECORDS STORAGE	CHASE TO BUILDING 32	DB-2	RECORDS STORAGE	X			GC-052	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY202A	017	01GA01	1	G	S0-09-1	STAIR #9		S0-09-1	STAIR #9				GA-016c	CAT6E
	018	01GA02	1	G	GA-027t	LOBBY		GA-027t	LOBBY				GA-016c	CAT6E
	019	01GA03	1	G		CONNECTING CORRIDOR			CONNECTING CORRIDOR	X			GA-016c	CAT6E
	020	01GA04	1	G	GA-027a	WAITING		GA-027a	WAITING	X			GA-016c	CAT6E
	021	01GA05	1	G	S0-02-1	STAIR #2		S0-02-1	STAIR #2				GA-016c	CAT6E
	022	01GA06	1	G	C0-05-1	CORRIDOR	ELECTRICAL, SIGNAL, AND TELE ROOM ENTRANCES	C0-05-1	CORRIDOR	X			GA-016c	CAT6E
	023	01GA07	1	G		SOUTH ELEC. SUBSTATION ENTRANCE	OUTDOOR COOLING TOWER		EXTERIOR	X			GA-016c	CAT6E
	024	01GA08	1	G	GA-027	PATIENT RECORD FILE ROOM		GA-027	PATIENT RECORD FILE ROOM	X			GA-016c	CAT6E
	025	01GA09	1	G	BA-023a	SHEET METAL SHOP (EAST)		BA-023a	SHEET METAL SHOP (EAST)	X			GA-016c	CAT6E
	026	01GA10	1	G	BA-023a	SHEET METAL SHOP (WEST)		BA-023a	SHEET METAL SHOP (WEST)	X			GA-016c	CAT6E
	027	01GA11	1	G		CONNECTING CORRIDOR			CONNECTING CORRIDOR	X			GA-016c	FOC
	028	01GA12	1	G	GA-023c	ELECTRICAL		GA-023c	ELECTRICAL	X			GA-016c	CAT6E
	029	01GA13	1	G	C0-05b-1	CORRIDOR	C0-05c-1	C0-05b-1	CORRIDOR				GA-016c	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY202B	030	01GB01	1	G		DOCK/METAL SHOP/SOUTH ELEC SUBSTATION ENTRANCES			EXTERIOR	X			GC-052	FOC
	031	01GB02	1	G		COMPUTER ROOM EXTERIOR			EXTERIOR	X			GC-052	FOC
	032	01GB03	1	G		COMP. ROOM / STAIRWELL / METAL DOCK EXTERIOR			EXTERIOR	X			GC-052	FOC
	033	01GB04	1	G	S0-04-1	STAIR #4		S0-04-1	STAIR #4				GC-052	FOC
	034	01GB05	1	G		WEST STAIR			WEST STAIR				GC-052	FOC
	035	01GB06	1	G	C0-01b-1	CORRIDOR	CORRIDORS C0-01-1 AND C0-02-1	C0-01b-1	CORRIDOR	X			GC-052	CAT6E
	036	01GB07	1	G		METAL DOCK			METAL DOCK	X			GC-052	FOC
	037	01GB08	1	G	C0-02-1	CORRIDOR		C0-02-1	CORRIDOR	X			GC-052	FOC
	038	01GB09	1	G	C0-04-1	CORRIDOR		C0-04-1	CORRIDOR	X			GC-052	FOC
	039	01GB10	1	G		STAIRS TO BASEMENT				X			GC-052	FOC
	040	01GB11	1	G	C0-01c-1	CORRIDOR		C0-01c-1	CORRIDOR	X			GC-052	CAT6E
	041	01GB12	1	G		STAIRS TO BASEMENT		GB-011	MECHANICAL				GC-052	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY202C	042	01GC01	1	G	S0-03-1	STAIR #3		S0-03-1	STAIR #3				GC-052	CAT6E
	043	01GC02	1	G	GC-002	ELEV. LOBBY	PHARMACY ENTRANCES, C0-07-1 CORRIDOR	GC-002	ELEV. LOBBY	X			GC-052	CAT6E
	044	01GC03	1	G		LOADING DOCK (WEST END)	CORRIDOR C0-07b-1, MED GAS / WAREHOUSE / KITCHEN ENTRANCES		LOADING DOCK (WEST END)	X			GC-052	CAT6E
	045	01GC04	1	G		RTU CORRIDOR			RTU CORRIDOR	X			GC-052	CAT6E
	046	01GC05	1	G	C0-19-1	CORRIDOR	WAITING AREA AND ELEVATOR LOBBY	C0-19-1	CORRIDOR	X			GC-052	CAT6E
	047	01GC06	1	G		MECHANICAL ROOM / STAIRWELL / WAREHOUSE ENTRANCES			EXTERIOR	X			GC-052	CAT6E
	048	01GC07	1	G	S0-20-1	STAIR #20		S0-20-1	STAIR #20				GC-052	CAT6E
	049	01GC08	1	G	GC-008	PHARMACY		GC-008	PHARMACY	X			GC-052	CAT6E
	050	01GC09	1	G	GC-008	PHARMACY		GC-008	PHARMACY	X			GC-052	CAT6E
	051	01GC10	1	G	GC-008	PHARMACY		GC-008	PHARMACY	X			GC-052	CAT6E
	052	01GC11	1	G		NORTH FACE OF C WING / WAREHOUSE OVERHEAD DOOR			EXTERIOR	X			GC-052	FOC
	053	01GC12	1	G		NORTH FACE OF C WING / TRASH COMPACTOR / LOADING DOCK			EXTERIOR	X			GC-052	FOC
	054	01GC13	1	G	S0-07-1	STAIR #7		S0-07-1	STAIR #7				GC-052	FOC
	055	01GC14	1	G	S0-XX-1	STAIR #XX (TO BASEMENT)		S0-XX-1	STAIR #XX (TO BASEMENT)				GC-052	FOC
	056	01GC15	1	G		TRASH COMPACTOR DOCK AREA	ENTRACE TO STAIR #XX (TO BASEMENT)		TRASH COMPACTOR DOCK AREA	X			GC-052	FOC
	057	01GC16	1	G		EXTERIOR ENTRANCE – WAREHOUSE ADDITION NORTHWEST			EXTERIOR ENTRANCE	X			GC-052	FOC
	058	01GC17	1	G	S0-12-1	STAIR #12	BASEMENT ACCESS	S0-12-1	STAIR #12	X			GC-052	FOC
	059	01GC18	1	G	C0-07a-1	CORRIDOR		C0-07a-1	CORRIDOR	X			GC-052	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY202D	060	01GD01	1	G	GD-007n	KITCHEN ENTRY		GD-007n	KITCHEN ENTRY	X			GD-039c	CAT6E
	061	01GD02	1	G		LOADING DOCK (EAST END)			LOADING DOCK (EAST END)	X			GD-039c	CAT6E
	062	01GD03	1	G		MORGUE CORRIDOR / ELECTRICAL ROOM ENTRANCES			EXTERIOR	X			GD-039c	FOC
	063	01GD04	1	G		RAMP TO BASEMENT			EXTERIOR				GD-039c	FOC
	064	01GD05	1	G	S0-22-1	STAIR #22		S0-22-1	STAIR #22				GD-039c	FOC
	065	01GD06	1	G		EAST FACE OF D WING – HVAC EQUIPMENT AND SPS ENTRANCE			EXTERIOR	X			GD-039c	FOC
	066	01GD07	1	G	S0-01-1	STAIR #1		S0-01-1	STAIR #1				GD-039c	CAT6E
	067	01GD08	1	G	C0-13-1	CORRIDOR		C0-13-1	CORRIDOR	X			GD-039c	CAT6E
	068	01GD09	1	G	GD-007	KITCHEN (ENTRANCE FROM CORRIDOR C0-12-1)		GD-007	KITCHEN				GD-039c	CAT6E
	069	01GD10	1	G	GD-007	KITCHEN (TWO ENTRANCES FROM CORRIDOR C0-06a-1)		GD-007	KITCHEN				GD-039c	CAT6E
	070	01GD11	1	G	GD-001	ELEVATOR LOBBY		GD-001	ELEVATOR LOBBY				GD-039c	CAT6E
	071	01GD12	1	G	C0-08-1	CORRIDOR (TO BLDG 30)		C0-08-1	CORRIDOR (TO BLDG 30)	X			GD-039c	CAT6E
	072	01GD13	1	G	GD-002	ELEVATOR LOBBY	CORRIDOR C0-06a-1 (ACCESS TO KITCHEN, SPD)	GD-002	ELEVATOR LOBBY	X			GD-039c	CAT6E
	073	01GD14	1	G		ELECTRICAL SUBSTATION			ELECTRICAL SUBSTATION	X			GD-039c	CAT6E
	074	01GD15	1	G	C0-16-1	CORRIDOR		C0-16-1	CORRIDOR	X			GD-039c	CAT6E
	075	01GD16	1	G	S0-08-1	STAIR #8		S0-08-1	STAIR #8				GD-039c	CAT6E
	076	01GD17	1	G		EXTERIOR GROUND LEVEL LOUVERS			EXTERIOR	X			GD-039c	FOC
	077	01GD18	1	G	C0-09-1	CORRIDOR	C0-05d-1 CORRIDOR	C0-09-1	CORRIDOR	X			GD-039c	CAT6E
	078	01GD19	1	G	GA-030	ELEVATOR LOBBY		GA-030	ELEVATOR LOBBY	X			GD-039c	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY203A	079	011E01	1	1		EMERGENCY DEPT EXTERIOR (SOUTH AND WEST ENTRANCES)			EXTERIOR	X			1A-113b	FOC
	080	011E02	1	1	1E-101	WAITING / TRIAGE AREA		1E-101	WAITING / TRIAGE AREA	X			1A-113b	FOC
	081	011E03	1	1		EMERGENCY DEPT SOUTH ENTRANCE		1E-101	WAITING / TRIAGE AREA			X	1A-113b	FOC
	082	011E04	1	1		EMERGENCY DEPT WEST ENTRANCE		1E-101	WAITING / TRIAGE AREA			X	1A-113b	FOC
	083	011E05	1	1	1E-146	NURSE STATION	V1-05-1 AMBULANCE ENTRANCE VESTIBULE	1E-146	NURSE STATION	X			1A-113b	FOC
	084	011E06	1	1	1E-146	NURSE STATION	V1-05-1 AMBULANCE ENTRANCE VESTIBULE	1E-146	NURSE STATION	X			1A-113b	FOC
	085	011E07	1	1	1E-147	MEDS		1E-147	MEDS	X			1A-113b	FOC
	086	011E08	1	1	V1-05-1	AMBULANCE/ER VESTIBULE		V1-05-1	AMBULANCE/ER VESTIBULE				1A-113b	FOC
	087	011A01	1	1		EXTERIOR AMBULANCE STAGING AREA			EXTERIOR	X			1A-113b	FOC
	088	011A02	1	1	1A-135	LOBBY		1A-135	LOBBY	X			1A-113b	FOC
	089	011A03	1	1	S1-09-1	STAIR #9		S1-09-1	STAIR #9				1A-113b	FOC
	090	011A04	1	1	C1-09-1	CORRIDOR	OPERATIONS ROOM, COMM ROOM AND EXTERIOR ENTRANCES	C1-09-1	CORRIDOR	X			1A-113b	CAT6E
	091	011A05	1	1	C1-0-1	CORRIDOR	WAITING AREAS 1A-115 AND 1A-155	C1-0-1	CORRIDOR	X			1A-113b	CAT6E
	092	011A06	1	1	S1-02-1	STAIR #2		S1-02-1	STAIR #2				1A-113b	CAT6E
	093	011A07	1	1	1A-176	INTERNAL MEDICINE WAITING		1A-176	INTERNAL MEDICINE WAITING	X			1A-113b	CAT6E
	094	011A08	1	1	1A-108d	PHARMACY STORAGE		1A-108d	PHARMACY STORAGE				1A-113b	CAT6E
	095	011A09	1	1	1A-108a	PHARMACY STORAGE		1A-108a	PHARMACY STORAGE	X			1A-113b	CAT6E
	096	011A10	1	1	1A-108a	PHARMACY STORAGE		1A-108a	PHARMACY STORAGE	X			1A-113b	CAT6E
	097	011A11	1	1	1A-108b	PHARMACY COMP		1A-108b	PHARMACY COMP				1A-113b	CAT6E
	098	011A12	1	1	V1-03-1	VESTIBULE		V1-03-1	VESTIBULE			X	1A-113b	CAT6E
	099	011A13	1	1	C1-04-1	CORRIDOR	ELEC/SIGNAL ROOM ENTRANCES	C1-04-1	CORRIDOR	X			1A-113b	CAT6E
	100	011A14	1	1		ELEVATOR LOBBY			ELEVATOR LOBBY	X			1A-113b	CAT6E
	101	011A15	1	1	1A-115A	COMM		1A-115A	COMM	X			1A-113b	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY203B	102	011B01	1	1	S1-04-1	STAIR #4		S1-04-1	STAIR #4				1C-101c	FOC
	103	011B02	1	1	S1-05-1	STAIR #5		S1-05-1	STAIR #5				1C-101c	FOC
	104	011B03	1	1	1B-156	WAITING		1B-156	WAITING	X			1C-101c	CAT6E
	105	011B04	1	1	C1-20-1	CORRIDOR	ELEC/SIGNAL ROOM ENTRANCES AND CORRIDOR C1-19a-1	C1-20-1	CORRIDOR	X			1C-101c	FOC
	106	011B05	1	1	C1-49-1	CORRIDOR	CI-18-1 CORRIDOR	C1-49-1	CORRIDOR	X			1C-101c	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY203C	107	011C01	1	1	S1-03-1	STAIR #3		S1-03-1	STAIR #3				1C-101c	CAT6E
	108	011C02	1	1	1C-101	ELEVATOR LOBBY		1C-101	ELEVATOR LOBBY	X			1C-101c	CAT6E
	109	011C03	1	1	S1-20-1	STAIR #20		S1-20-1	STAIR #20				1C-101c	CAT6E
	110	011C04	1	1	CC-1	CORRIDOR		CC-1	CORRIDOR	X			1C-101c	CAT6E
	111	011C05	1	1	S1-06-1	STAIR #6		S1-06-1	STAIR #6				1C-101c	FOC
	112	011C06	1	1	C1-29-1	CORRIDOR	1C-107 WAITING, 1C-131 RECEPTION	C1-29-1	CORRIDOR	X			1C-101c	CAT6E
	113	011C07	1	1	S1-07-1	STAIR #7		S1-07-1	STAIR #7				1C-101c	FOC
	114	011C08	1	1	1C-158	WAITING		1C-158	WAITING	X			1C-101c	CAT6E
	115	011C09	1	1	1C-159	WAITING		1C-159	WAITING	X			1C-101c	CAT6E
	116	011C10	1	1	C1-30-1	CORRIDOR	CORRIDOR C1-31-1	C1-30-1	CORRIDOR	X			1C-101c	FOC
	117	011C11	1	1	C1-34-1	CORRIDOR	CORRIDOR C1-32-1	C1-34-1	CORRIDOR	X			1C-101c	FOC
	118	011C12	1	1	C1-35-1	CORRIDOR	CORRIDOR C1-36-1	C1-35-1	CORRIDOR	X			1C-101c	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY203D	119	011D01	1	1	1D-104	PHARMACY		1D-104	PHARMACY	X			1D-131b	CAT6E
	120	011D02	1	1	1D-103	ELEVATOR LOBBY		1D-103	ELEVATOR LOBBY	X			1D-131b	CAT6E
	121	011D03	1	1	1D-1XX	ELEVATOR LOBBY		1D-1XX	ELEVATOR LOBBY	X			1D-131b	CAT6E
	122	011D04	1	1	1D-127	X-RAY WAITING	1D-133 X-RAY RECEPTION, C1-40-1 CORRIDOR	1D-127	X-RAY WAITING	X			1D-131b	CAT6E
	123	011D05	1	1	S1-01-1	STAIR #1		S1-01-1	STAIR #1				1D-131b	CAT6E
	124	011D06	1	1	S1-22-1	STAIR #22		S1-22-1	STAIR #22				1D-131b	FOC
	125	011D07	1	1	1D-181	WAITING		1D-181	WAITING	X			1D-131b	CAT6E
	126	011D08	1	1	V1-02-1	VESTIBULE		V1-02-1	VESTIBULE			X	1D-131b	CAT6E
	127	011D09	1	1	V1-10-1	VESTIBULE		V1-10-1	VESTIBULE			X	1D-131b	CAT6E
	128	011D10	1	1	1D-101	MAIN LOBBY		1D-101	MAIN LOBBY	X			1D-131b	CAT6E
	129	011D11	1	1		EXTERIOR – FRONT ENTRANCE			EXTERIOR – FRONT ENTRANCE	X			1D-131b	CAT6E
	130	011D12	1	1	C1-43-1	CORRIDOR	CORRIDOR C1-50-1	C1-43-1	CORRIDOR	X			1D-131b	CAT6E
	131	011D13	1	1	C1-44-1	CORRIDOR	CORRIDOR C1-42-1	C1-44-1	CORRIDOR	X			1D-131b	CAT6E
	132	011D14	1	1	1D-196d	WASTE/AUTOCLAVE		1D-196d	WASTE/AUTOCLAVE	X			1D-131b	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE

1.EY204A	133	012A01	1	2	S2-09-1	STAIR #9		S2-09-1	STAIR #9				2A-213c	CAT6E
	134	012A02	1	2	2A-230	WAITING		2A-230	WAITING	X			2A-213c	CAT6E
	135	012A03	1	2	C2-03-1	CORRIDOR	C2-04-1 CORRIDOR	C2-03-1	CORRIDOR	X			2A-213c	CAT6E
	136	012A04	1	2	2A-214a	FOOD COURT		2A-214a	FOOD COURT	X			2A-213c	CAT6E
	137	012A05	1	2	C2-01-1	CORRIDOR	C2-02-1 CORRIDOR	C2-01-1	CORRIDOR	X			2A-213c	CAT6E
	138	012A06	1	2	2A-215a	CANTEEN OFFICE		2A-215a	CANTEEN OFFICE	X			2A-213c	CAT6E
	139	012A07	1	2	2A-201	RETAIL STORE		2A-201	RETAIL STORE	X			2A-213c	CAT6E
	140	012A08	1	2	2A-242	ELEVATOR LOBBY		2A-242	ELEVATOR LOBBY	X			2A-213c	CAT6E
	141	012A09	1	2	C2-04a-1	CORRIDOR (VESTIBULE FROM USF CORRIDOR)		C2-04a-1	CORRIDOR			X	2A-213c	CAT6E
	142	012A10	1	2	C2-04a-1	USF CORRIDOR		C2-04a-1	CORRIDOR	X			2A-213c	CAT6E
	143	012A11	1	2	S2-02-1	STAIR #2		S2-02-1	STAIR #2				2A-213c	CAT6E
	144	012A12	1	2	2A-244a	CANTEEN GENERAL STORAGE		2A-244a	CANTEEN GENERAL STORAGE	X			2A-213c	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY204B	145	012B01	1	2	S2-04-1	STAIR #4		S2-04-1	STAIR #4				2C-201c	FOC
	146	012B02	1	2	S2-05-1	STAIR #5		S2-05-1	STAIR #5				2C-201c	FOC
	147	012B03	1	2	2B-254	FAMILY WAITING		2B-254	FAMILY WAITING	X			2C-201c	CAT6E
	148	012B04	1	2	C2-15-1	CORRIDOR	C2-14-1 CORRIDOR	C2-15-1	CORRIDOR	X			2C-201c	FOC
	149	012B05	1	2	C2-13-1	CORRIDOR	C2-14-1 CORRIDOR	C2-13-1	CORRIDOR	X			2C-201c	FOC
	150	012B06	1	2	C2-19-1	CORRIDOR	2B-254 FAMILY WAITING	C2-19-1	CORRIDOR	X			2C-201c	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY204C	151	012C01	1	2	S2-03-1	STAIR #3		S2-03-1	STAIR #3				2C-201c	CAT6E
	152	012C02	1	2	2C-201	ELEVATOR LOBBY		2C-201	ELEVATOR LOBBY	X			2C-201c	CAT6E
	153	012C03	1	2	S2-06-1	STAIR #6		S2-06-1	STAIR #6				2C-201c	FOC
	154	012C04	1	2	S2-07-1	STAIR #7		S2-07-1	STAIR #7				2C-201c	FOC
	155	012C05	1	2	C2-33-1	CORRIDOR	2C-276b COMPUTER ROOM ENTRANCE, 2D-215 UPS ENTRANCE	C2-33-1	CORRIDOR	X			2C-201c	CAT6E
	156	012C06	1	2	C2-23-1	CORRIDOR	C2-24-1 CORRIDOR	C2-23-1	CORRIDOR	X			2C-201c	FOC
	157	012C07	1	2	C2-22-1	CORRIDOR	C2-30-1 CORRIDOR	C2-22-1	CORRIDOR	X			2C-201c	CAT6E
	158	012C08	1	2	C2-28-1	CORRIDOR	C2-27-1 CORRIDOR	C2-28-1	CORRIDOR	X			2C-201c	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY204D	159	012D01	1	2	2D-204	ELEVATOR LOBBY		2D-204	ELEVATOR LOBBY	X			2D-255b	CAT6E
	160	012D02	1	2	2D-256	SICU & SURGERY WAITING		2D-256	SICU & SURGERY WAITING	X			2D-255b	CAT6E
	161	012D03	1	2	S2-01-1	STAIR #1		S2-01-1	STAIR #1				2D-255b	CAT6E
	162	012D04	1	2	2D-202	ELEVATOR LOBBY		2D-202	ELEVATOR LOBBY	X			2D-255b	CAT6E
	163	012D05	1	2	S2-22-1	STAIR #22		S2-22-1	STAIR #22				2D-255b	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY206	164	013A01	1	3	S3-02-1	STAIR #2		S3-02-1	STAIR #2				3A-325d	CAT6E
	165	013A02	1	3	3A-336	ELEVATOR LOBBY		3A-336	ELEVATOR LOBBY	X			3A-325d	CAT6E
	166	013A03	1	3	3A-335	ELEVATOR LOBBY		3A-335	ELEVATOR LOBBY	X			3A-325d	CAT6E
	167	013A04	1	3	3A-340	WAITING ROOM		3A-340	WAITING ROOM	X			3A-325d	CAT6E
	168	013A05	1	3	3A-344	RECEPTION/CHARTING		3A-344	RECEPTION/CHARTING	X			3A-325d	CAT6E
	169	013A06	1	3	S3-01-1	STAIR #1		S3-01-1	STAIR #1				3A-325d	CAT6E
	170	013A07	1	3	3A-331	FAMILY WAITING		3A-331	FAMILY WAITING	X			3A-325d	CAT6E
	171	013A08	1	3		UTILITY ROOM ENTRANCES		3A-335	CORRIDOR	X			3A-325d	CAT6E
	172	013B01	1	3	3A-3XX	ELEVATOR LOBBY		3A-3XX	ELEVATOR LOBBY	X			3A-325d	CAT6E
	173	013B02	1	3	3B-306	RECEPTION		3B-306	RECEPTION	X			3A-325d	CAT6E
	174	013B03	1	3		CORRIDOR	ENTRANCES TO UTILITY ROOMS		CORRIDOR	X			3A-325d	CAT6E
	175	013B04	1	3	S3-03-1	STAIR #3		S3-03-1	STAIR #3				3A-325d	CAT6E
	176	013B05	1	3	3B-313	MECHANICAL		3B-313	MECHANICAL	X			3A-325d	CAT6E
	177	013B06	1	3	3B-316	STORAGE		3B-316	STORAGE	X			3A-325d	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY207	178	014A01	1	4	S4-02-1	STAIR #2		S4-02-1	STAIR #2				4A-425d	CAT6E
	179	014A02	1	4	4A-430	PYXIS		4A-430	PYXIS	X			4A-425d	CAT6E
	180	014A03	1	4	4A-436	ELEVATOR LOBBY		4A-436	ELEVATOR LOBBY	X			4A-425d	CAT6E
	181	014A04	1	4	4A-435	ELEVATOR LOBBY		4A-435	ELEVATOR LOBBY	X			4A-425d	CAT6E
	182	014A05	1	4	S4-01-1	STAIR #1		S4-01-1	STAIR #1				4A-425d	CAT6E
	183	014A06	1	4	C4-07-1	CORRIDOR		C4-07-1	CORRIDOR	X			4A-425d	CAT6E
	184	014A07	1	4	C4-01-1	CORRIDOR		C4-01-1	CORRIDOR	X			4A-425d	CAT6E
	185	014A08	1	4		UTILITY ROOM ENTRANCES		C4-05-1	CORRIDOR	X			4A-425d	CAT6E
	186	014B01	1	4	4B-401	ELEVATOR LOBBY		4B-401	ELEVATOR LOBBY	X			4A-425d	CAT6E
	187	014B02	1	4	S4-03-1	STAIR #3		S4-03-1	STAIR #3				4A-425d	CAT6E
	188	014B03	1	4	4B-423	WAITING		4B-423	WAITING	X			4A-425d	CAT6E
	189	014B04	1	4	C4-10-1	CORRIDOR		C4-10-1	CORRIDOR	X			4A-425d	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY208	190	015A01	1	5	S5-02-1	STAIR #2		S5-02-1	STAIR #2				5A-525d	CAT6E
	191	015A02	1	5	5A-536	ELEVATOR LOBBY		5A-536	ELEVATOR LOBBY	X			5A-525d	CAT6E
	192	015A03	1	5	5A-535	ELEVATOR LOBBY		5A-535	ELEVATOR LOBBY	X			5A-525d	CAT6E
	193	015A04	1	5	S5-01-1	STAIR #1		S5-01-1	STAIR #1				5A-525d	CAT6E
	194	015A05	1	5	5A-548	PYXIS		5A-548	PYXIS	X			5A-525d	CAT6E
	195	015A06	1	5	C5-07-1	CORRIDOR		C5-07-1	CORRIDOR	X			5A-525d	CAT6E
	196	015A07	1	5	C5-01-1	CORRIDOR		C5-01-1	CORRIDOR	X			5A-525d	CAT6E
	197	015A08	1	5		UTILITY ROOM ENTRANCES		C5-05-1	CORRIDOR	X			5A-525d	CAT6E
	198	015B01	1	5	5B-5XX	ELEVATOR LOBBY		5B-5XX	ELEVATOR LOBBY	X			5A-525d	CAT6E
	199	015B02	1	5	S5-03-1	STAIR #3		S5-03-1	STAIR #3				5A-525d	CAT6E
	200	015B03	1	5	5B-526	PYXIS		5B-526	PYXIS	X			5A-525d	CAT6E
	201	015B04	1	5	C5-10-1	CORRIDOR	UTILITY CLOSET ENTRANCES	C5-10-1	CORRIDOR	X			5A-525d	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY209	202	016A01	1	6	S6-02-1	STAIR #2		S6-02-1	STAIR #2				6A-625d	CAT6E
	203	016A02	1	6	6A-607	MEDICATION ROOM		6A-607	MEDICATION ROOM	X			6A-625d	CAT6E
	204	016A03	1	6	6A-635	ELEVATOR LOBBY		6A-635	ELEVATOR LOBBY	X			6A-625d	CAT6E
	205	016A04	1	6	6A-636	ELEVATOR LOBBY		6A-636	ELEVATOR LOBBY	X			6A-625d	CAT6E
	206	016A05	1	6	6A-640	SHARED WAITING		6A-640	SHARED WAITING	X			6A-625d	CAT6E
	207	016A06	1	6	S6-01-1	STAIR #1		S6-01-1	STAIR #1				6A-625d	CAT6E
	208	016A07	1	6	C6-01-1	CORRIDOR		C6-01-1	CORRIDOR	X			6A-625d	CAT6E
	209	016A08	1	6	C6-07-1	CORRIDOR		C6-07-1	CORRIDOR	X			6A-625d	CAT6E
	210	016A09	1	6		UTILITY ROOM ENTRANCES		C6-05-1	CORRIDOR	X			6A-625d	CAT6E
	211	016B01	1	6	6B-600	ELEVATOR LOBBY		6B-600	ELEVATOR LOBBY	X			6A-625d	CAT6E
	212	016B02	1	6	S6-03-1	STAIR #3		S6-03-1	STAIR #3				6A-625d	CAT6E
	213	016B03	1	6	6B-622	WAITING		6B-622	WAITING	X			6A-625d	CAT6E
	214	016B04	1	6	C6-11-1	CORRIDOR	UTILITY CLOSET ENTRANCES	C6-11-1	CORRIDOR	X			6A-625d	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY210	215	017A01	1	7	S7-02-1	STAIR #2		S7-02-1	STAIR #2				7A-722c	CAT6E
	216	017A02	1	7	S7-01-1	STAIR #1		S7-01-1	STAIR #1				7A-722c	CAT6E
	217	017A03	1	7	7A-731a	SATELLITE PHARMACY		7A-731a	SATELLITE PHARMACY	X			7A-722c	CAT6E
	218	017A04	1	7	7A-731	ELEVATOR LOBBY		7A-731	ELEVATOR LOBBY	X			7A-722c	CAT6E
	219	017A05	1	7	7A-730	ELEVATOR LOBBY		7A-730	ELEVATOR LOBBY	X			7A-722c	CAT6E
	220	017A06	1	7	C7-01-1	CORRIDOR		C7-01-1	CORRIDOR	X			7A-722c	CAT6E
	221	017A07	1	7	C7-07-1	CORRIDOR		C7-07-1	CORRIDOR	X			7A-722c	CAT6E
	222	017A08	1	7		UTILITY ROOM ENTRANCES		C7-05-1	CORRIDOR	X			7A-722c	CAT6E
	223	017B01	1	7	7B-701	ELEVATOR LOBBY		7B-701	ELEVATOR LOBBY	X			7A-722c	CAT6E
	224	017B02	1	7	S7-03-1	STAIR #3		S7-03-1	STAIR #3				7A-722c	CAT6E
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
1.EY212	225	01PA01	1	P		PENTHOUSE EXTERIOR AND ROOF			PENTHOUSE EXTERIOR	X			7A-722c	FOC
	226	01PA02	1	P		PENTHOUSE EXTERIOR AND ROOF			PENTHOUSE EXTERIOR	X			7A-722c	FOC
	227	01PA03	1	P		PENTHOUSE EXTERIOR AND ROOF			PENTHOUSE EXTERIOR	X			7A-722c	FOC
	228	01PA04	1	P		PENTHOUSE EXTERIOR AND ROOF			PENTHOUSE EXTERIOR	X			7A-722c	FOC
	229	01PA05	1	P	SP-03-1	STAIR #3		SP-03-1	STAIR #3				7A-722c	FOC
	CAM CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE

FULLY SPRINKLERED
BID DOCUMENTS
FOR CONSTRUCTION

Revisions: | Date

CONSULTANTS:

ARCHITECT/ENGINEERS:

paradigm
Architecture | Engineering | Design-Build
9 Oak Drive, Ocala, FL 34472 – www.paradigmusa.com

June 2017
STATE OF KENTUCKY
BLAINE CAMIEL VAN GANSBEKE
24,768
LICENSED
PROFESSIONAL ENGINEER

Drawing Title: COMPLETE VASS MATRIX BUILDING 1

Approved Project Director

Project Title: UPGRADE FACILITIES SECURITY

Location: JAMES A. HALEY VAMC
13000 BRUCE B. DOWNS BLVD., TAMPA, FL 33612

Date: 06-01-2017 | Checked: WLM | Drawn: MMF

Project Number: 673-14-100

Building Number: VARIES

Drawing Number: EY601

Office of Construction and Facilities Management

Department of Veterans Affairs

30.EY201A
30.EY201B

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
230	30GA01	30	G		ELECTRICAL ROOM ENTRANCES	SOUTH SIDE OF BUILDING 64 ELEC. SUBSTATION		EXTERIOR	X			30-0861	CAT6E
231	30GA02	30	G		ELECTRICAL ROOM ENTRANCES	CLC COURTYARD		EXTERIOR	X			30-0861	CAT6E
232	30GA03	30	G		30-01-30 STAIR EXIT	GARNET PARKING LOT		EXTERIOR	X			30-0861	CAT6E
233	30GA04	30	G	30-03A-30	FUTURE STAIRWELL #3		30-03A-30	FUTURE STAIRWELL #3				30-0861	FOC
234	30GA05	30	G		CO-07-30 CORRIDOR EXIT	MECHANICAL ROOM ENTRANCE		EXTERIOR	X			30-0861	FOC
235	30GA06	30	G	30-02-30	STAIR #2		30-02-30	STAIR #2				30-0861	CAT6E
236	30GA07	30	G	30-051b	EXTERIOR COURTYARD (EAST)		30-051b	EXTERIOR COURTYARD (EAST)	X			30-0861	CAT6E
237	30GA08	30	G	30-086	RECEPTION/NURSE STATION	C0-04-30 CORRIDOR	C0-04-30	CORRIDOR	X			30-0861	CAT6E
238	30GA09	30	G	30-000	ELEVATOR LOBBY		30-000	ELEVATOR LOBBY	X			30-0861	CAT6E
239	30GA10	30	G	30-01-30	STAIR #1		30-01-30	STAIR #1				30-0861	CAT6E
240	30GA11	30	G	30-025	ELECTRICAL		30-025	ELECTRICAL				30-0861	CAT6E
241	30GA12	30	G	30-059	ELECTRICAL		30-059	ELECTRICAL				30-0861	CAT6E
242	30GA13	30	G		COURTYARD			EXTERIOR	X			30-0861	CAT6E
243	30GA14	30	G		SOUTH COURTYARD			SOUTH COURTYARD	X			30-0861	CAT6E
244	30GA15	30	G	30-096	OPERATORS		30-096	OPERATORS	X			30-0861	CAT6E
245	30GA16	30	G	C0-01-30	CORRIDOR	C0-02-30 CORRIDOR	C0-01-30	CORRIDOR	X			30-0861	CAT6E

30.EY202

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
246	301A01	30	1		SOUTH & WEST SIDES OF BLDG. NO. 64 ELEC. SUBSTATION	VALET ENTRANCE		EXTERIOR	X			30-165	CAT6E
247	301A02	30	1		NORTH & EAST SIDES OF BLDG. NO. 64 ELEC. SUBSTATION			EXTERIOR	X			30-165	CAT6E
248	301A03	30	1		WEST SIDE OF BLDG. 30 AND CHASE ENTRANCE	VALET ENTRANCE		EXTERIOR	X			30-165	CAT6E
249	301A04	30	1	S1-2-30	STAIR #2		S1-2-30	STAIR #2				30-165	CAT6E
250	301A05	30	1	30-101	MAIN ENTRANCE (SALLIE PORT)		30-101	MAIN ENTRANCE (SALLIE PORT)	X			30-165	CAT6E
251	301A06	30	1	30-101	MAIN LOBBY		30-101	MAIN LOBBY				30-165	CAT6E
252	301A07	30	1	C1-01-30	CORRIDOR		C1-01-30	CORRIDOR				30-165	CAT6E
253	301A08	30	1	30-100	ELEVATOR LOBBY		30-100	ELEVATOR LOBBY	X			30-165	CAT6E
254	301A09	30	1	C1-03-30	CORRIDOR	30-166 RESIDENT LOUNGE	C1-03-30	CORRIDOR	X			30-165	CAT6E
255	301A10	30	1	S1-1-30	STAIR #1		S1-1-30	STAIR #1				30-165	CAT6E
256	301A11	30	1	S1-3-30	STAIR #3		S1-3-30	STAIR #3				30-165	CAT6E

30.EY203

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
257	302A01	30	2	S2-3-30	STAIR #3		S2-3-30	STAIR #3				30-265	CAT6E
258	302A02	30	2	S2-1-30	STAIR #1		S2-1-30	STAIR #1				30-265	CAT6E
259	302A03	30	2	S2-2-30	STAIR #2		S2-2-30	STAIR #2				30-265	CAT6E
260	302A04	30	2	30-241	MED ROOM		30-241	MED ROOM	X			30-265	CAT6E
261	302A05	30	2	C2-02-30	CORRIDOR	30-266 RESIDENT LOUNGE	C2-02-30	CORRIDOR	X			30-265	CAT6E
262	302A06	30	2	30-200	ELEVATOR LOBBY		30-200	ELEVATOR LOBBY	X			30-265	CAT6E
263	302A07	30	2	30-220	MED ROOM		30-220	MED ROOM	X			30-265	CAT6E

30.EY204

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
264	303A01	30	3	53-3-30	STAIR #3		53-3-30	STAIR #3				30-366a	CAT6E
265	303A02	30	3	53-1-30	STAIR #1		53-1-30	STAIR #1				30-366a	CAT6E
266	303A03	30	3	53-2-30	STAIR #2		53-2-30	STAIR #2				30-366a	CAT6E
267	303A04	30	3	30-341	MEDICATION ROOM		30-341	MEDICATION ROOM	X			30-366a	CAT6E
268	303A05	30	3	C3-02-30	CORRIDOR	30-366 LIVING SPACE	C3-02-30	CORRIDOR	X			30-366a	CAT6E
269	303A06	30	3	30-300	ELEVATOR LOBBY		30-300	ELEVATOR LOBBY	X			30-366a	CAT6E
270	303A07	30	3	C3-05-30	CORRIDOR	UTILITY ROOM ENTRANCE	C3-05-30	CORRIDOR	X			30-366a	CAT6E

32.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
271	32BA01	32	B		RAMP TO BASEMENT (EAST SIDE OF BLDG 32)			EXTERIOR				B-23	CAT6E
272	32BA02	32	B	32-B19	EMS STORAGE AND WORK AREA		32-B19	EMS STORAGE AND WORK AREA				B-23	CAT6E
273	32BA03	32	B	50-1-32	STAIR #1		50-1-32	STAIR #1				B-23	CAT6E
274	32BA04	32	B		TUNNEL TO BLDG 1			TUNNEL TO BLDG 1				B-23	CAT6E
275	32BA05	32	B		SOUTH ENTRANCE			EXTERIOR				B-23	CAT6E

32.EY202

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
276	32GA01	32	G	50-01-32	STAIR #1		50-01-32	STAIR #1				32-039	CAT6E
277	32GA02	32	G		NORTHEAST ENTRANCE			EXTERIOR				32-039	CAT6E
278	32GA03	32	G	50-02-32	STAIR #2		50-02-32	STAIR #2				32-039	CAT6E
279	32GA04	32	G		SOUTHEAST ENTRACNE			EXTERIOR				32-039	CAT6E
280	32GA05	32	G		SOUTH ENTRANCE			EXTERIOR				32-039	CAT6E
281	32GA06	32	G	32-026b	CHECK IN	CONTROL ROOM ENTRANCES	32-026b	CHECK IN	X			32-039	CAT6E
282	32GA07	32	G	32-030	WAITING ROOM	ENTRANCE FROM BLDG. 38	32-030	WAITING ROOM	X			32-039	CAT6E
283	32GA08	32	G		BLDG 32 CORRIDOR FROM STAIR #1			BLDG 32 CORRIDOR FROM STAIR #1			X	32-039	CAT6E
284	32GA09	32	G		BLDG 32 EXTERIOR ENTRANCE			BLDG 32 EXTERIOR ENTRANCE			X	32-039	CAT6E
285	32GA10	32	G		CORRIDOR			CORRIDOR	X			32-039	CAT6E

32.EY203

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
286	321A01	32	1	51-01-32	STAIR #1		51-01-32	STAIR #1				32-127	CAT6E
287	321A02	32	1	51-02-32	STAIR #2		51-02-32	STAIR #2				32-127	CAT6E
288	321A03	32	1	C1-01-32	CORRIDOR / ELEVATOR LOBBY		C1-01-32	CORRIDOR / ELEVATOR LOBBY	X			32-127	CAT6E
289	321A04	32	1	C1-01-CC	CONNECTING CORRIDOR		C1-01-CC	CONNECTING CORRIDOR				32-127	CAT6E
290	321A05	32	1	32-101	MULTIPURPOSE ROOM (COOP)		32-101	MULTIPURPOSE ROOM (COOP)	X			32-127	CAT6E
291	321A06	32	1	C1-02-32	CORRIDOR (DIRECTOR SUITE, NORTH)		C1-02-32	CORRIDOR (DIRECTOR SUITE)	X			32-127	CAT6E
292	321A07	32	1	C1-02-32	CORRIDOR (DIRECTOR SUITE, SOUTH)		C1-02-32	CORRIDOR (DIRECTOR SUITE)	X			32-127	CAT6E
293	321A08	32	1	C1-07-32	CORRIDOR		C1-07-32	CORRIDOR	X			32-127	CAT6E
294	321A09	32	1	32-138	VESTIBULE TO MECHANICAL ROOM		32-138	VESTIBULE TO MECHANICAL ROOM				32-127	CAT6E
295	321A10	32	1	C1-05-32	CORRIDOR	C1-03-32 CORRIDOR	C1-05-32	CORRIDOR	X			32-127	CAT6E
296	321A11	32	1	C1-05-32	CORRIDOR	EAST ENTRANCE TO DIRECTORS SUITE	C1-05-32	CORRIDOR				32-127	CAT6E

39.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
297	391A01	39	1		WEST SIDE OF BLDG. 39			EXTERIOR	X			39-A207	CAT6E
298	391A02	39	1		NORTH SIDE OF BLDG. 39			EXTERIOR	X			39-A207	CAT6E
299	391A03	39	1		EAST SIDE OF BLDG. 39			EXTERIOR	X			39-A207	CAT6E
300	391A04	39	1		SOUTH SIDE OF BLDG. 39			EXTERIOR	X			39-A207	CAT6E
301	391A05	39	1	39-A107	ENGINEERING CONTROL ROOM		39-A107	ENGINEERING CONTROL ROOM	X			39-A207	CAT6E
302	391A06	39	1		WEST MAN DOOR			EXTERIOR			X	39-A207	CAT6E
303	391A07	39	1		NORTH SIDE OF BLDG. 39			EXTERIOR	X			39-A207	CAT6E

54.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
304	541A01	54	1		NORTHEAST SIDE OF BLDG. 54			EXTERIOR	X			004a	CAT6E
305	541A02	54	1		SOUTHEAST SIDE OF BLDG. 54			EXTERIOR	X			004a	CAT6E
306	541A03	54	1		SOUTHWEST SIDE OF BLDG. 54			EXTERIOR	X			004a	CAT6E
307	541A04	54	1		NORTHWEST SIDE OF BLDG. 54			EXTERIOR	X			004a	CAT6E
308	541A05	54	1		WEST MAN DOOR			EXTERIOR			X	004a	CAT6E
309	541A06	54	1	54-001	COURTYARD (WEST)		54-001	COURTYARD (WEST)	X			004a	CAT6E
310	541A07	54	1	54-001	COURTYARD (EAST)		54-001	COURTYARD (EAST)	X			004a	CAT6E
311	541A08	54	1	54-004	PLANT OFFICES		54-004	PLANT OFFICES	X			004a	CAT6E
312	541A09	54	1	54-004	PLANT OFFICES		54-004	PLANT OFFICES	X			004a	CAT6E
313	541A10	54	1		EAST MAN DOOR			EXTERIOR			X	004a	CAT6E
314	541A11	54	1		SOUTH SIDE OF BLDG. 54	STORAGE TRAILERS IN PEARL PARKING LOT		EXTERIOR	X			004a	CAT6E

LI.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
315	LIGA01	LI			LIBERTY LOT NORTH ENTRANCE (VEHICLE/PED)						X		FOC
316	LIGA02	LI			LIBERTY LOT EAST ENTRANCE (PED)						X		FOC
317	LIGA03	LI			LIBERTY LOT WEST ENTRANCE (PED)						X		FOC
318	LIGA04	LI			LIBERTY LOT SOUTH ENTRANCE (PED)						X		FOC
319	LIGA05	LI			LIBERTY LOT INTERIOR				X				FOC
320	LIGA06	LI			LIBERTY LOT NORTH PERMETER				X				FOC
321	LIGA07	LI			LIBERTY LOT NORTH PERIMETER				X				FOC
322	LIGA08	LI			LIBERTY LOT EAST PERIMETER				X				FOC
323	LIGA09	LI			LIBERTY LOT NORTH ENTRANCE (PED)						X		FOC
324	LIGA10	LI			LIBERTY LOT EAST PERIMETER				X				FOC
325	LIGA11	LI			LIBERTY LOT SOUTH PERIMETER				X				FOC
326	LIGA12	LI			LIBERTY LOT WEST PERIMETER				X				FOC
327	LIGA13	LI			LIBERTY LOT INTERIOR				X				FOC
328	LIGA14	LI			LIBERTY LOT INTERIOR				X				FOC
329	LIGA15	LI			LIBERTY LOT NORTH ENTRANCE (VEHICLE/PED)					X			FOC

FR.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
330	FRGA01	FR			FREEDOM LOT NORTH ENTRANCE (VEHICLE/PED)					X		FRFS01	FOC
331	FRGA02	FR			FREEDOM LOT EAST ENTRANCE (PED)						X	FRFS01	FOC
332	FRGA03	FR			FREEDOM LOT SOUTHEAST ENTRANCE (PED)						X	FRFS01	FOC
333	FRGA04	FR			FREEDOM LOT SOUTH CENTRAL ENTRANCE (PED)						X	FRFS01	FOC
334	FRGA05	FR			FREEDOM LOT SOUTH CENTRAL ENTRANCE (VEHICLE)						X	FRFS01	FOC
335	FRGA06	FR			FREEDOM LOT NORTHWEST PERIMETER				X			FRFS01	FOC
336	FRGA07	FR			FREEDOM LOT NORTH PERIMETER				X			FRFS01	FOC
337	FRGA08	FR			FREEDOM LOT NORTH PERIMETER				X			FRFS01	FOC
338	FRGA09	FR			FREEDOM LOT NORTH PERIMETER				X			FRFS01	FOC
339	FRGA10	FR			FREEDOM LOT EAST PERIMETER				X			FRFS01	FOC
340	FRGA11	FR			FREEDOM LOT NORTH ENTRACNE (VEHICLE/PED)						X	FRFS01	FOC
341	FRGA12	FR			FREEDOM LOT SOUTH PERIMETER				X			FRFS01	FOC
342	FRGA13	FR			FREEDOM LOT SOUTH CENTRAL ENTRANCE (VEHICLE)						X	FRFS01	FOC
343	FRGA14	FR			FREEDOM LOT INTERIOR				X			FRFS01	FOC
344	FRGA15	FR			FREEDOM LOT NORTH ENTRACNE (PED)						X	FRFS01	FOC
345	FRGA16	FR			FREEDOM LOT INTERIOR				X			FRFS01	FOC
346	FRGA17	FR			FREEDOM LOT INTERIOR				X			FRFS01	FOC

RO.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
347	ROGA01	RO			ROMEO LOT NORTHWEST ENTRANCE (VEHICLE/PED)					X		ROFS01	FOC
348	ROGA02	RO			ROMEO LOT SOUTHEAST ENTRANCE (PED)					X		ROFS01	FOC
349	ROGA03	RO			ROMEO LOT SOUTHWEST ENTRANCE (PED)					X		ROFS01	FOC
350	ROGA04	RO			ROMEO LOT WEST ENTRANCE (PED)					X		ROFS01	FOC
351	ROGA05	RO			ROMEO LOT NORTH PERIMETER				X			ROFS01	FOC
352	ROGA06	RO			ROMEO LOT INTERIOR				X			ROFS01	FOC
353	ROGA07	RO			ROMEO LOT EAST PERIMETER				X			ROFS01	FOC
354	ROGA08	RO			ROMEO LOT SOUTH PERIMETER				X			ROFS01	FOC
355	ROGA09	RO			ROMEO LOT WEST PERIMETER				X			ROFS01	FOC
356	ROGA10	RO			ROMEO LOT WEST PERIMETER				X			ROFS01	FOC
357	ROGA11	RO			ROMEO LOT INTERIOR				X			ROFS01	FOC
358	ROGA12	RO			FREEDOM LOT NORTH ENTRACNE (VEHICLE/PED)					X		ROFS01	FOC

EM.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
359	EMGA01	EM			EMERALD LOT				X			EMFS01	FOC
360	EMGA02	EM			EMERALD LOT				X			EMFS01	FOC
361	EMGA03	EM			EMERALD LOT				X			EMFS01	FOC
362	EMGA04	EM			EMERALD LOT				X			EMFS01	FOC

PE.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
363	PEGA01	PE			PEARL LOT				X			004a (BLDG 54	FOC
364	PEGA02	PE			PEARL LOT				X			004a (BLDG 54	FOC
365	PEGA03	PE			PEARL LOT				X			004a (BLDG 54	FOC

SA.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
366	SAGA01	SA			SAPPHIRE LOT				X			EMFS01	FOC
367	SAGA02	SA			SAPPHIRE LOT				X			EMFS01	FOC
368	SAGA03	SA			SAPPHIRE LOT				X			EMFS01	FOC
369	SAGA04	SA			SAPPHIRE LOT				X			EMFS01	FOC
370	SAGA05	SA			SAPPHIRE LOT				X			EMFS01	FOC

PR.EY201

CT.	CAM ID	BLDG	FLOOR	COVERAGE (ROOM NO.)	COVERAGE (ROOM NAME)	ADDITIONAL COVERAGE	LOCATION (ROOM NO.)	LOCATION (ROOM NAME)	360°	LPR	FR	IT ROOM	CABLE
371	PRGA01				CAMPUS PERIMETER					X		39-A207	FOC
372	PRGA02				CAMPUS PERIMETER					X		39-A207	FOC
373	PRGA03				CAMPUS PERIMETER					X		39-A207	FOC
374	PRGA04				CAMPUS PERIMETER						X	39-A207	FOC
375	PRGA05				CAMPUS PERIMETER					X		39-A207	FOC
376	PRGA06				CAMPUS PERIMETER						X	39-A207	FOC
377	PRGA07				CAMPUS PERIMETER						X	39-A207	FOC
378	PRGA08				CAMPUS PERIMETER					X		39-A207	FOC
379	PRGA09				CAMPUS PERIMETER					X		39-A207	FOC
380	PRGA10				CAMPUS PERIMETER						X	39-A207	FOC
381	PRGA11				CAMPUS PERIMETER					X		39-A207	FOC
382	PRGA13				CAMPUS PERIMETER					X		004a (BLDG 54	FOC
383	PRGA14				CAMPUS PERIMETER						X	304a (BLDG 54	FOC
384	PRGA15				CAMPUS PERIMETER				X			004a (BLDG 54	FOC
385	PRGA16				CAMPUS PERIMETER				X			004a (BLDG 54	FOC
386	PRGA17				CAMPUS PERIMETER				X			004a (BLDG 54	FOC
387	PRGA18				CAMPUS PERIMETER				X			004a (BLDG 54	FOC
388	PRGA19				CAMPUS PERIMETER				X			004a (BLDG 54	FOC
389	PRGA20				CAMPUS PERIMETER				X			004a (BLDG 54	FOC
390	PRGA21				CAMPUS PERIMETER				X			004a (BLDG 54	FOC
391	PRGA22				CAMPUS PERIMETER				X			004a (BLDG 54	FOC

FULLY SPRINKLERED
BID DOCUMENTS
FOR CONSTRUCTION

Revisions	Date

CONSULTANTS:

ARCHITECT/ENGINEERS:

paradigm
Architecture | Engineering | Design-Build
9 Oak Drive, Ocala, FL 34472 – www.paradigmusa.com

STATE OF KENTUCKY
BLAINE CAMIEL VAN GANSBEKE
24,769
LICENSED
PROFESSIONAL ENGINEER

Drawing Title: COMPLETE VASS MATRIX BUILDINGS 30, 32, 39, 54, PARKING LOTS AND PERIMETER

Approved Project Director:

Project Title: UPGRADE FACILITIES SECURITY

Location: JAMES A. HALEY VAMC, 13000 BRUCE B. DOWNS BLVD., TAMPA, FL 33612

Date: 06-01-2017 | Checked: WLM | Drawn: MMF

Project Number: 673-14-100

Building Number: VARIES

Drawing Number: EY602

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08-6231